PT. YONGJIN JAVASUKA GARMENT	**INSTRUKSI KERJA PENARIKAN KEBOCORAN SEAM SEALING - *WORK INSTRUCTION RECALL SEAMSEALING LEAKAGE***	No. Dokumen : YJ-IK.QA.0004 Tgl. Efektif : 21 Februari 2018 No. Revisi : 01 Halaman : 1

1 Setelah proses cross bar, setiap garment harus dipasang tali rafia, untuk melacak output tiap jam, warna rafia harus berbeda untuk output tiap jam.

All garments after cross seam press must have color tie (Rafia) to trace the garments of particular one hour output. (identification as one batch output)

2 Selain dari memasang rafia dengan warna yang berbeda tiap jam di setiap garment, operator crossbar harus mencatat output crossbar setiap jam.

Aside from putting color tie on each garments, Cross seam press operator must also have counter (record) to quantify how many output have finished within 1 hour.

3 Proses test air dilakukan setiap jam, setiap garment yang akan di test harus di dinginkan terlebih dahulu minimum 20 menit setelah crossbar.

Sutter test conducted every 1 hour, the piece to be tested should be cooled down at least minimum of 20 minutes after curing time

4 Jika terjadi kebocoran ketika test air, operator test air harus ambil secara acak 2 pcs dari warna rafia yang sama dan lakukan test di posisi yang bocor. Dengan mengikuti langkah - langkah dibawah ini :

If in case there's failed sutter test, operator need to conduct randomly another 2 pcs sutter testing to particular failed point, these 2 pcs should be taken from identified one batch output (same color tie code) following below steps

a) Jika dari hasil test 2 pcs tersebut masih ditemukan bocor, maka semua output di jam tersebut (warna rafia yang sama) harus di test ulang 100% dan di perbaiki.

a) if the additional 2 pcs test still have one failed point, all one batch output need to be recalled for testing and rectification

b) Jika hasil test 2 pcs tersebut OK, maka semua output di jam tersebut (warna rapia sama) bisa lanjut ke proses berikutnya. Dan 1 pcs yang sebelumnya FAIL harus diperbaiki.

b) if the additional 2 pcs test all passed, those one batch can proceed on assembly and the one piece which previously failed need to be fixed.

c) Jika hasil test OK, tapi di jam - jam berikutnya ditemukan bocor di posisi yang sama, maka semua output di jam tersebut harus ditarik untuk di test ulang dan di perbaiki.

c) if the succeeding sutter test within the same day have another failure on the same point, the entire one batch output need to be tested and rectified.

d) Jika terjadi kebocoran, operator harus lapor dan memanggil SPV QC dan mekanik.

d) if there's a failed sutter test, operator need to raised alert by calling the line supervisor/QC head and mechanic.

5 Sebelum proses assembly dan join lining, 100% garment harus di check kualitas seam sealing nya oleh QC.

100% checking on seam sealing should be conducted prior to send the outer shell for assembly/attach lining.